



## CLARK COUNTY

### SMALL WORKS QUOTE #0399 LEWISVILLE PARK PLAY EQUIPMENT REMOVAL

#### QUESTIONS and ANSWERS

UPDATED: APRIL 8, 2025

	QUESTION	ANSWER
1.	Do we place and compact topsoil to fill the voids from the footings or is the expectation for the entire playground area to get a skiff of topsoil and graded out?	Fill the voids from the footings.
2.	Will there be any straw and seeding?	No seeding is included in this contract.
3.	Are footing sizes known?	No. We have no design drawing records for this equipment.
4.	Can work be completed before October?	The project must be bid per the bid documents. After award, the contractor may request specific dates to complete the work sooner. The County will evaluate the request at that time based upon a number of factors.
5.	Is rock backfill acceptable in lieu of topsoil?	Yes, rock backfill is acceptable, the top 6" must be clean topsoil as described in the bid documents.